

### Schedule of works

#### Upon arrival

Check for fault conditions on control panel

#### Control panel

Check internal control components

Check lamps

Check sounder

Check stepping relay (if applicable)

Check battery condition (if applicable)

#### Pump chamber

Check access cover

Check pump station chamber

Wash down chamber walls (where possible)

#### Filter

Check access cover (if applicable)

Check leaf filter

Remove debris and wash down leaf filter (where possible)

Check and clear micro filter (if applicable)

#### Level controls

Check level controls

Check level controls sequence

#### Pump/s

Check for blockages

Check impellor rotation (only three phase)

Check fluids (oil, coolant)

Check moving parts (rotor, bearings)

Check resistance with electrical meter

Check amp draw with electrical meter

Wash down pump/s

#### Access equipment

Check top bracket/s

Check guide rail/s

Check lifting chain/s

Check shackles

### NOTES

### Schedule of works

#### Pipework and valves

Check internal pipework/fittings

Check valves (non-return and gate valves)

Check valves are clear of debris

Wash down internal pipework

Wash down valves

#### Header tank

Check header tank (if applicable)

Check level controls (if applicable)

Remove debris and wash down (where possible)

Check valves (if applicable)

#### UV system

Check UV system (if applicable)

Check UV lamp run time (if applicable)

Check valves (if applicable)

#### Expansion Vessel

Check expansion vessel (if applicable)

Check integrity of vessel bladder (if applicable)

Check valves (if applicable)

#### Final

Wet test system

Check pump/s running in Auto mode

Check pump/s impellor rotation correct (only three phase)

Check control panel closed and switched On/System Switched On

Check access cover replaced and secured

### Excluded

All connecting pipework/fittings to and from the chamber/sump

Incoming power supply

*Edincare may be unable to inspect all aspects of the equipment due to, for example, inaccessibility of equipment, adverse weather conditions, or where the customer has not followed the installation guidelines. Edincare Terms and Conditions apply.*